

REQUEST FOR QUOTATION

INSTRUCTIONS

STO-93 REV - 2/90
(Stock No. 6938-069-01)

Please quote us your prices on the commodities listed below. All prices must be F.O.B. Destination and you must show Unit Price, Amount, and Total or bid may be rejected.

Since the State of Connecticut is exempt from the payment of Federal Excise Taxes and the Connecticut Sales Tax, do not include such taxes.

The undersigned bidder affirms and declares: That this quotation is executed and signed by said bidder with full knowledge and acceptance of the provisions of Form SP-7A of current issue and in effect on the date of bid issue. Form SP-7A, entitled Standards Bid and Contract Terms and Conditions, together with the Commodity Specifications, Proposal Schedule, and Special Bid and Contract Terms and Conditions are made a part of this request for quotation.

Bidder's Name & Address:

This is not an order. Fill and return to STATE OF CONNECTICUT at the address shown below.

ISSUED BY (Agency) Dept. of Mental Retardation, North Region		(Return bid attention of) Tina Jordan	BID NO. AND OR REQUISITION NO. DMR 7003
AGENCY ADDRESS 255 Pitkin Street, East Hartford, CT 06108		DATE ISSUED May 15, 2007	DATE AND TIME BID REQUIRED 6/15/07 @ 2 PM
SIGNED (For Agency) <i>Tina P. Jordan</i>	TITLE Fiscal Administrative Officer	TELEPHONE NO. & EXTENSION 860-263-2550	DATE MATERIAL REQUIRED see sheet

ITEM NO.	Description	UNIT	QUANTITY	To be completed by bidder.	
				Unit Price	Amount
	Camp Quinebaug - Greenhouse *see attached scope of work*				
	Provide and install 30' X 60' greenhouse				
1	Complete greenhouse installed with Double IR/AC poly	1	unit		
2	Complete greenhouse installed with Corrugated Polycarbonate 8mm	1	unit		
3	Shade Cloth - 36' X 60', 50% shade cloth with taped edges and grommets	1	ea		
4	Mist System - per scope	1	ea		
5	Cost of replacement - Double IR/AC poly - when needed	1	ea		
6	*Attach sheet with requirements for concrete slab including dimentions*				
*	Please attach a separate sheet separating the price of the greenhouse & labor for information only per scope of work				
7	Lead time needed from issuance of Purchase Order to start work	Days			
	Mandatory site visit June 8, 2007 at 9:00AM				
*	54 Taos Drive, Danielson, CT 06239				
	The department reserves the right to accept or reject any or all of the bid if deemed to be in the best interests of the Dept and/or State of CT.				

To be completed by bidder	QUOTATION NO.	DATE SUBMITTED	DELIVERY AS REQ'D. ABOVE (Unless noted here)			TOTAL
	SIGNED	TITLE	TELEPHONE NO. AND EXTENSION	CASH DISCOUNT ____% ____ days,	PAYMENT TERMS NET 45 DAYS	
	VENDOR FEIN/SSN	ARE YOU INCORPORATED <input type="checkbox"/> YES <input type="checkbox"/> NO	PURCHASE ORDER ADDRESS (If different from bidder's address above)			

Scope of Work

Provide and install 30' x 60' Greenhouse at Camp Quinebaug, 54 Taos Drive, Danielson, CT. meeting the following specifications.

Specifications

Frame

Size - 30' wide by 60' long, New England or Northern Star or equal.

Bows – galvanized tubing, gothic truss frame 1.9" diameter x 13 gage. Minimum vertical height on sidewall – 4'. Bows need flat plate at base for attachment to slab floor

Wind bracing on corners

Metal end wall framing for polycarbonate glazing

Doors – two ADA commercial grade, pre-hung 42" insulated utility doors with weather-stripping and window

Design load - Snow load – 30 pounds/sq ft - Wind load – 100 mph

Glazing

Roof/sides - 6-mil double IR/AC poly

Wiggewire aluminum extrusion attachment

End walls - 8 mm clear, structured polycarbonate sheet with UV stabilizer and condensation control

"H" and "h" extrusions for attaching polycarbonate

Tek screws with neoprene bonded washers

Solid foil tape for top of sheets and perforated tape for bottom for condensation control.

Silicone Caulk

Heater

Propane fired gas heater such as Modine PD200 or approved equal capable of providing 160,000 Btu/hr.

Equipment shall include a heater hanger and vent pipe kit. Thermostat for control.

Provide one Universal 250 propane gas heater for emergency backup heat.

Cooling

Manual roll-up sides to 4' above ground.

Fans - Two 30" – ½ hp fans, one with a 1-speed motor, one with a 2-speed motor, slant housing and guard

Voltage – 115/230 single phase.

Two-36" motorized intake shutters - 115 volt, one single stage and one two stage thermostats.

Air circulation

Two – 12" diameter, 1/10 hp circulating fans with mounting bracket, 1725 rpm, 1650 cfm, 115/230 volt.

Schaefer Manufacturing Co. Model VS12PA or J&D Manufacturing Model VBG12 or approved equal.

Provide alternate pricing for the following:

Erection of greenhouse - attach separate sheet with these three prices

Labor for erection of greenhouse on supplied floating slab

Labor for installation of double poly.

Labor for installation of Corrugated Polycarbonate.

Shade cloth One - 36' x 60', 50% shade cloth with taped edges and grommets.

Mist system

The system contains piping, fittings, nozzles, solenoid, wire and controller for one bench.

Provide heat mats for under flats.

Glazing

Provide Corrugated Polycarbonate 8mm instead of double poly.

The following will be provided by others, unless otherwise specified.

1. Site preparation and concrete slab
2. Electrical service and wiring.
3. Water service and plumbing.
4. Telephone Service and internal wiring.
5. Heater and fan installations.
6. Main propane tank and associated piping to heaters.

Contact information for any questions:

Warren G. Schilling, P.E.

Plant Facilities Engineer

State of Connecticut, DMR North Region

155 Founders Plaza, 255 Pitkin Street

East Hartford, CT 06108

Voice (860) 263-2486

Fax (860) 263-2525

Email: warren.schilling@po.state.ct.us